ENGINEERING DEPARTMENT.

KOLAR DIVISION.

Notice dated 10th January 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. of 4th February 1929, for constructing a new tank across Vrishabavati near Kamasamudram, Bowringpet Taluk. An approximate estimate of quantities are given below. These quantities are not guaranteed. The work should be completed by the end of June 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two thousand only (Rs. 2000) in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for constructing a new tank across the Vrishabavati near Kamasamudram", in default of which, tenders will be rejected. After the tender is accepted, the balance amount of earnest money, calculated at 5 per cent of the sanctioned estimate amount should be deposited by the successful tenderer.

5. The final acceptance of any tender will be rest with the Government, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate rate will not be accepted.

Abstract estimate of constructing a new tank across Vrishabhavati near Kamasamudram Bowringpet Taluk.

	Items of work	Per	Quantity	Rate	Cost	Total
	Bund.			Rs.	Rs.	
1.	Clearing sand	Lump	sum			
2.	Removing seat of bund top soil ...	C.yd.	16,815			
3.	Cutting trenches below bund ...	,,	1,857			
4.	Earthwork to bund with watering and tamping, with all lead and lift, etc.	,,	1,07,176			
5.	Earthwork available from seat of bund ...	,,	16,815			
6.	Do from spoil of weir cutting including watering and tamping.	,,	3,1415			
7.	Gravel backing and spreading over bund ...	,,	4,369			
8.	Turfing	S.yd.	13,847			
9.	Benching rock	S.ft.	1,782			
10.	Burnt brick in surki mortar ...	C.ft.	4,158			
11.	Rough stone revetment	C.yd.	11,377			
12.	Grade stones with index and bed stones ...	No.	23			
13.	Register No. Stone	,,	1			
14.	B. M. Stones	,,	2			
15.	Gauge stones	,,	4			
16.	Date stone	,,	1			
17.	Dry stone toes	C.yd.	3,366			
18.	Baling water	Lump	sum			
19.	Jelly drains	Lump	sum			
20.	Temporary weir during execution ...	Lump	sum			
21.	Clearing jungle	Lump	sum			
	Total to Bund ...	...	...	...	...	...

Items of work	Per	Quantity	Rate	Cost	Total
Sluice.			Rs.	Rs.	Rs.
22. Earthwork	C.yd.	114			
23. Burnt brick in surki mortar	C.ft.	12,489			
24. Burnt stone slabs 6″ thick	S.ft.	445			
25. Do 4″ do	,,	396			
26. Do 9″ do	,,	5			
27. Plastering with surki mortar	Sqr.	11·60			
28. Cutting orifice	Lump	sum			
29. Plug with rod complete	Lump	sum			
30. Shutters with rod	Lump	sum			
31. Railing to steps	Lump	sum			
32. Teakwood beams	C.ft.	9			
33. Roughly dressed burnt stone in mortar ...	,,	270			
34. Gravel backing	C.yd.	11			
Total to Sluice ...	...	..	...	..	...
Waste Weir.					
1. Earthwork excavation	C.yd.	13,464			
2. Soft rock excavation	,,	17,951			
3. Burnt brick in surki mortar	C.ft.	5,395			
4. Burnt stone slabs 6″ well dressed ...	S.ft.	1646			
5. Rough stone apron	C.yd.	600			
6. Plastering with surki mortar .	Sqr.	7·00			
7. Chunam concrete	C.ft.	2610			
8. Joggle joints	No.	100			
Total of weir ...	...	...	...	...	...
Total of Bund, Sluice and waste weir ...	...	.	..	...	...
Contingencies at 5 % ...	..	...	...	...	..
Grand Total ...	...	...	..	...	...

Notice dated 9th January 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M. of 4th February 1929, for restoring Talakunte Kondlukere and Talakunte Royarakere, Malur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred and fifty in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Talakunte Kondlukere and Talakunte Royarakere" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9' The tenderers must quote specific rates for each item of work both in words and figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate rate will not be accepted.

Detailed abstract estimate for restoring Talkunte Rayarakere and Talkunte Kondalkere Registered No. 461 of Malur Taluk.

Items No.	Items of work	Per	Rate	Quantity	Cost
	TALKUNTE RAYARAKERE.				
	Bund.				
1	Earthwork including watering and tamping with lead and lift, etc., complete.	C.yds.		2,428	
2	Turfing	S.yds.		2,429	
3	New stone work	C.yds.		233	
4	Fixing new grade stones including figuring and painting, etc., complete.	No.		13	
5	Fixing index stones including figuring and painting, etc., complete.	,,		13	
6	Fixing Registered No. stones including figuring and painting, etc., complete.	,,		1	
7	Fixing B. M. stones including figuring and painting, etc., complete.	,,		2	
8	Fixing guage stones including figuring and painting, etc., complete.	,,		1	
9	Cutting Hongey trees wherever found necessary and rooting them out including jungle clearing if any.	L. S.		...	
	Total bund ...	...		..	
	Sluice.				
1	Patch repairs existing sluice found necessary during execution providing plug and rod with locking arrangements.	L. S.		...	
	Total sluice ...	...		...	
	Waste Weir.				
1	Earthwork excavation in hard soil ...	C.yds.		658	
2	Surki concrete	C.ft.		262	
3	Burnt brick in surki mortar	,,		515	
4	Burnt stone slabs 6" thick	S.ft.		365	
5	Surki mortar plastering	Sqr.		7·15	
6	New stone work	C.yds.		59	
7	Joggle joints with cement pointing, etc., complete.	No.		10	
	Total waste weir ...	...		...	
	Grand Total ...	...		...	
	TALAKUNTE KONDALKERE.				
	Bund.				
1	Earthwork including waterings tamping with lead and lift, etc., complete.	C.yds.		3,713	
2	Turfing	S.yds.		3,119	
3	Resetting old stone with new jelly ...	C.yds.		299	
4	New stone work	,,		656	
5	Fixing Grade stones including figurings and painting.	No.		14	
6	Fixing Index stones including figuring and painting.	,,		14	
7	Fixing Register No. and date stone including figuring and painting.	,,		1	
8	Fixing B. M. stones including figuring and painting.	,,		2	
9	Fixing Guage stone including figuring and painting.	,,		1	
	Total ...		...	...	..

Item No.	Items of work	Per	Rate	Quantity	Cost
	Sluice.				
1	Earthwork excavation	C.yds.		45	
2	Refilling with waterings tamping	,,		50	
3	Surki concrete	C.ft.		198	
4	Burnt brick in surki mortar	,,		172	
5	Burnt stone slabs 6″ thick	S.ft.		178	
6	Surki mortar plastering	Sqs.		3·59	
7	Providing plug and rod with locking arrangements.	L. S.		...	
8	Drilling holes in cross and orrifice slabs ...	,,		...	
	Total sluice ...	...		...	
	Waste weir.				
1	Earthwork	C.yds.		53	
2	Concrete in surki mortar	C.ft.		165	
3	Burnt brick in surki mortar	,,		351	
4	Burnt stone slabs	S.ft.		223	
5	Surki mortar plastering	S.qr.		6·20	
6	New stone work	C.yds.		23	
	Total weir ...	...		...	
	Grand Total ...	...		...	
	Total of both the tanks ...	...		...	
	Contingencies ...	...		...	
	Grand Total ...	...		...	

Notification dated 24th December 1928.

The attention of the public is invited to the notification published in the *Mysore Gazette* Part VI, pages 25—26, calling for tenders for restoring Geraddi Tank, Regd., No. 48 of Sidlaghatta Taluk. Last date of tender, 24th January 1929.

Notice dated 26th December 1928.

The attention of the public is invited to the notification published in the *Mysore Gazette* Part VI, pages 5—6, calling for tenders for restoring Rampur Ramasayi Tank, Regd No. 40 of Goribidnur Taluk. Last date of tender is 29th January 1929.

Dated 9th January 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 P.M., of 4th February 1929 for Restoring Chickapayalagurki Tank Registered No. 137 of Chickballapur Taluk. An approximate estimate of quantities are given below. These quantities are not guaranteed. The work should be completed by the end of December 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rupees one hundred and seventy in cash or Government Promissory Notes as earnest money, and be superscribed "Tenders for Restoring Chickapayalagurki Tank Registered No. 137 of Chickballapur Taluk" in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond ; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's office in due course. No enquiries regarding the accptance or rejection of a tender will receive any reply.

8. On a cceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and figures.

10. Tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate rate will not be accepted.

Detailed abstract estimate for restoring Chickpayalgurki Tank Registered No. 137 of Chikballapur Taluk.

No.	Items of work	Per	Rate	Quantity	Cost
	Bund.				
1	Earthwork including watering and tamping ..	C.yds.		4,055	
2	Turfing	S.yds.		4,007	
3	Resetting oldstone with new jelly	L. S.		...	
4	New stone work	C.yds.		178	
5	Fixing B. M. stones with figuring and painting, etc., complete.	No.		2	
6	Fixing new grade stones do ...	,,		2	
7	Refixing old grade stone with chiselling figures painting, etc., complete.	,,		10	
8	Fixing new index stones	,,		12	
9	,, Registered No. Stone painting, etc., complete.	,,		1	
10	,, Guage stone painting, etc., complete	,,		1	
11	Cutting grips removing prickly pears and removing anthills, etc.	Grade		10	
	Total Bund ..				
	SluiceNo. 1.				
1	Dismantling the existing sluice at weir ...	L. S.		...	
2	Earthwork	C.yds.		114	
3	Refilling gap	,,		84	
4	Surki concrete	C.ft.		234	
5	Burnt brick in surki mortar	,,		653	
6	Removing and refixing available Gibet slabs ..	L. S.		...	
7	Burnt stone slabs	Sft.		224	
8	Surki mortar plastering	Sqr.		7·24	
9	Providing plug and rod with locking arrangements	L. S.		..	
	Total ...				

No.	Items of work	Per	Rate	Quantity	Cost
	Sluice No. 2.				
1	Examining and repairing the sluice and providing plug and rod with locking arrangements.	L. S.		..	
	Weir No. 1 or left.				
1	Dismantling apron, etc.	C.yds.		39	
2	Removing coping slabs of existing weir ...	L. S.		...	
3	Burnt brick in surki mortar	Cft.		60	
4	Burnt stone slabs of 6" thick	S.ft.		114	
5	Refixing old available slabs	,,		46	
6	Surki mortar plastering	Sqr.		2·03	
7	New stone work	C.yd.		110	
8	Old stone work	,,		35	
	Total left weir ...				
	Weir No. 2 or right.				
1	Removing by dismantling the existing right end of return.	L. S.		...	
2	Removing the existing apron	C.yd.		18	
3	Earthwork	,,		189	
4	Surki concrete	C.ft.		49	
5	Burnt brick in surki mortar	,,		109	
6	New slabs coping	S.ft.		31	
7	Resetting old available slabs	,,		36	
8	Surki mortar plastering	Sqr.		0·74	
9	New stone work	C.yd.		27	
10	Resetting old stone with new jelly	,,		18	
	Total right weir ...				
	Distribution.				
	Constructing a slabbed aqueduct on stone pillars with masonry side walls.	L. S.			

Dated 9th January 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division, up to 2 p.m. of 4th February 1929, for constructing a new tank at Thippaganahalli, Goribidnur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A. M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rupees. Two thousand only for the present in cash or Government Promissory Notes, as earnest money, and be superscribed.

"Tender for constructing a new Thippaganahalli Tank, Goribidnur Taluk, in default of which, tenders will be rejected. After the tender is accepted the balance amount of earnest money calculated at 5 per cent of the sanctioned estimate amount should be deposited by the successful tenderer.

5. The final acceptance of any tender will rest with the Governmet, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderer must quote specific rates for each item of work both in words and figures.

10. The tenderers stating that the work would be executed at a certain percentage in excess or lower than the estimate will not be accepted.

Abstract estimate for constructing New Thippaganahalli Tank, Goribidnur Taluk.

Items of works	Per	Quantity	Rate	Cost	Total
Bund to R. L. 75.00 :—			Rs. a. p.		
1. Earthwork, watering and tamping with all lead and lift etc., complete.	C.yd.	1,59,551			
2. Removing surface soil and silt for foundation of bund and using the same for rear slope.	,,	2,625			
3. Removing silt and sand from bed of river.	,,	5,923			
4. Bailing water	Lumpsum				
5. Turfing	Sq.yds.	17,678			
6. Gravel backing to revetment ..	C.yd.	3,031			
7. New stone work	,,	10,469			
8. Grade stones with index and bed stones.	No.	29			
9. Benchmark stones.. ...	,,	2			
10. Register No. stone... ...	,,	1			
11. Guage stone	,,	2			
12. Excavating and benching rock for core wall.	Lumpsum				
13. Burnt brick in surki mortar for core wall.	C.ft.	7,277			
14. Deep pointing with surki mortar	Sqr.	29·40			
Total for bund ...	...	...			

	Items of works	Per	Quantity	Rate	Cost	Total
				Rs. a. p.		
	Sluice to R. L. 42·00.					
1.	Concrete in surki mortra ...	C.ft.	4,112			
2.	Brick do ...	,,	12,984			
3.	Plastering with two coats of chunam mortar.	Sqr.	23·09			
4.	Burnt stone slabs 4½" thick ...	Sq.ft.	802			
5.	Do 7" to 9" thick ...	,,	138			
6.	Cutting orifices, etc. ...	Lump	sum			
7.	Fixing one shutter with gearing rod, etc.	,,	,,			
8.	Fixing one plug with chains etc.,	,,	,,			
9.	Archwork	C.ft.	16			
10.	Rubble stone flooring in rear ...	C.yd.	12			
	Total for sluice ...	...	...	...	...	..
	Waste weir 175' long.					
1.	Concrete in surki mortar ...	C.ft.	888			
2.	Burnt brick in surki mortar ...	C.ft.	2,171			
3.	Burnt stone slabs 4" thick ...	Sq.ft.	841			
4.	Rough stone work ...	C.yd.	298			
	Distribution sluice channel.					
1.	Earthwork excavation ...	Cyd.	2,000			
2.	Irrigation culverts across Bangalore-Hindupur road.	No.	4			
3.	Masonry or rough stone work at crossings of drainages.	Lump	sum			
4.	Putting earthenware pipes for channel Bidigandies.	,,	,,			
	Divertion of road.					
1.	Earthwork embankment ...	Cyd.	3,533			
2.	Cutting ordinary soil ...	,,	993			
3.	Cutting gravelly soil ..	,,	217			
	Constructing road dam.					
1.	Earthwork excavation chargeable to road.					
2.	Burnt brick in surki mortar ...	C.ft.	1,653			
3.	Burnt stone slabs 4½" thick ...	Sq.ft.	378			
4.	Rubble stone flooring ..	Cyd.	144			
	Construction of tunnels 1 vent by 2¾ × 3½, 3½ × 5¾, 3½ × 5¾.					
1.	Earthwork chargeable to road ..					
2.	Burnt stone in mortar ...	C.ft.	2,719			
3.	Burnt brick in chunam mortar	,,	334			
4.	Burnt stone slabs 6" thick ...	Sq.ft.	393			
5.	Do 3" ,, ...	,,	182			
6.	Caps on termination of wings ..	Each	12			
7.	Pointing with chunam mortar...	Sqr.	14·70			
8.	Plastering with chunam mortar	,,	5·35			
9.	Rough stone flooring with jelly packing.	C.yd.	11			
10.	Guard stones ..	No.	12			

Items of work	Per	Quantity	Rate	Cost	Total
Adding one vent to Bridge in 7 3/6 of Bangalore-Hindupur road.			Rs. a. p.		
1. Earthwork chargeable to road...					
2. Dismantling masonry work ...	C.ft.	778			
3. Concrete in surki mortar ...	„	191			
4. Brick in surki mortar ...	„	1,521			
5. Archwork in surki mortar ...	C.ft.	624			
6. Burnt stone slabs 4" thick dressed	Sq. ft.	81			
7. Plastering with surki mortar ...	Sqr.	10·72			
Mettalling and drainage etc., for diverting Bangalore Hindupur road from 2/35 to 2/36.					
1. Drainage... Earthwork excavation ..	C.yds.	5,882			
2. Mettalling complete ...	C.yd.	972			
3. Gravelling complete ...	„	1,459			
4. Sanding complete ...	„	324			
5. Removing and refixing furlong stones.	No.	7			
6. New furlong stone ...	„	1			
7. New tunnel stone ...	„	1			
Total ...	...	...	...	...	..
Total of all the works ...	...	...	...	...	...
Contingencies ...	...	...	...	...	...
Grand total ...	...	...	...	....	...

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

TUMKUR DIVISION.

Dated 12th January 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Tumkur Division, up to 2nd February 1929, for constructing a Travellers' Bungalow and out-houses at Pavagada, Tumkur District. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 15th May 1929.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Tumkur between the hours of 11 A.M. to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

3a. Percentage rates will not be accepted.

4. Each tender must be accompanied by a deposit of rupees four hundred only in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing a Travellers Bungalow and out-houses at Pavagada, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.